



NOTES:

- 1) ADDITIONAL PERIMETER HALF SHEETS MAY BE REQUIRED. CONSULT FLEX TECHNICAL DEPARTMENT.
- 2) INTERIOR SHEETS ARE TO RUN PERPENDICULAR TO THE DIRECTION OF STEEL AND PLANK DECKS. PERIMETER HALF SHEETS WIDER THEN 3' MAY NOT BE INSTALLED PARALLEL TO THE STEEL DECK RIBS. REFER TO FACTORY MUTUAL LPDS 1-29
- 3) SHINGLE LAPS WITH FLOW OF WATER WHERE POSSIBLE.
- 4) CONSULT FLEX TECHNICAL DEPARTMENT FOR ACCEPTABLE FLASHING SUBSTRATES.

TITLE		PERIMETER SHEET EDGE	
NAME		DETAIL NO. 6.40	
DRAWN BY:	SK	DATE:	8/2012
APPLICABLE TO FLEX			
MECHANICALLY FASTENED SYSTEMS			
FLEX MEMBRANE INTERNATIONAL		2670 LEISCZ'S BRIDGE RD. LEESPORT, PA 19533 800-969-0108 FlexRoofingSystems.com	