



NOTES:

1) ADDITIONAL PERIMETER HALF SHEETS MAY BE REQUIRED. CONSULT FLEX TECHNICAL DEPARTMENT.

2) INTERIOR SHEETS ARE TO RUN PERPENDICULAR TO THE DIRECTION OF STEEL AND PLANK DECKS. PERIMETER HALF SHEETS WIDER THEN 3' MAY NOT BE INSTALLED PARALLEL TO THE STEEL DECK RIBS. REFER TO FACTORY MUTUAL LPDS 1-29

3) SHINGLE LAPS WITH FLOW OF WATER WHERE POSSIBLE.

| | | |
|-------------------------------|--|--------------|
| TITLE | PERIMETER SHEET WALL | |
| NAME | DETAIL NO. 6.50 | |
| DRAWN BY: | SK | DATE: 8/2012 |
| APPLICABLE TO FLEX | | |
| MECHANICALLY FASTENED SYSTEMS | | |
| FLEX MEMBRANE INTERNATIONAL | 2670 LEISCZ'S BRIDGE RD. LEESPORT, PA 19533 800-969-0108 FlexRoofingSystems.com | |