



NOTES:

1) ADDITIONAL PERIMETER HALF SHEETS MAY BE REQUIRED. CONSULT FLEX TECHNICAL DEPARTMENT.

2) INTERIOR SHEETS ARE TO RUN PERPENDICULAR TO THE DIRECTION OF STEEL AND PLANK DECKS. PERIMETER HALF SHEETS WIDER THEN 3' MAY NOT BE INSTALLED PARALLEL TO THE STEEL DECK RIBS. REFER TO FACTORY MUTUAL DATA SHEET 1-29

3) SHINGLE LAPS WITH FLOW OF WATER WHERE POSSIBLE.

TITLE		PERIMETER SHEET WALL	
NAME		DETAIL NO. 6.50	
DRAWN BY:	SK	DATE:	1/2018
APPLICABLE TO ALL FLEX			
MECHANICALLY ATTACHED SYSTEMS			
FLEX MEMBRANE INTERNATIONAL		2670 LEISCZ'S BRIDGE RD. LEESPORT, PA 19533 800-969-0108 FlexRoofingSystems.com	