

FLEX WALL FLASHING MEMBRANE ADHERED

WELD THE OVERLAPPING SHEET A MIN. 2" PAST THE IN SEAM FASTENING

WALL HEIGHTS GREATER THAN 4 FT.

FLEX TERMINATION BAR OR FLEX PLATES AND FASTENERS FASTENED 12" O.C. INSIDE THE SEAM SPACED APART 76" MAX

FLEX FIELD MEMBRANE ADHERED

76" MAX

6" MIN

APPROVED SUBSTRATE

FLEX SPECIFIED SECUREMENT

HOT AIR WELD MIN. 2"

DECK

WALL HEIGHTS 4 FT AND GREATER

TITLE	
WALL FLASHING - STRAPPED METHOD	
NAME	
DETAIL NO. 2.60	
DRAWN BY:	DATE:
SK	7/2017
APPLICABLE TO ALL FLEX	
ADHERED ROOFING SYSTEMS	
FLEX MEMBRANE INTERNATIONAL	2670 LEISCZ'S BRIDGE RD. LEESPORT, PA 19533 800-969-0108 FlexRoofingSystems.com

